

Table 7-15 Summary of K_0 -Consolidated Undrained Triaxial Tests
EAST CONTRACT
Brightwater Conveyance System

Boring No.	Sample Top Depth (ft)	Elevation (ft) ^a	Geologic Unit	σ_v (ksf)	σ_h (ksf)	K_0	Initial Conditions			After Consolidation			Failure @ R_{max} ^b				Failure @ q_{max} ^c				E_i ^d (ksf)	E_{50} ^e (ksf)
							W (%)	γ_{dry} (pcf)	e	W (%)	γ_{dry} (pcf)	e	p (ksf)	p' (ksf)	q_{max} (ksf)	A_f	p (ksf)	p' (ksf)	q_{max} (ksf)	A_f		
BRIGHTWATER TUNNEL 1																						
E-334	167.0	22.5	Qpfnl	5.0	3.55	0.7	25.0	100.6	0.74	25.8	100.6	0.71	8.4	7.0	4.9	0.15	10.3	10.7	6.7	(0.03)	1,204	530
E-334	167.3	22.2	Qpfnl	14.9	5.65	0.4	25.6	103.8	0.72	25.5	103.8	0.65	14.5	14.4	8.9	0.01	16.3	18.2	10.7	(0.09)	2,191	1,382
E-334	167.6	21.9	Qpfnl	29.9	10.83	0.4	25.6	102.4	0.73	25.7	102.4	0.68	23.3	23.1	12.4	0.01	24.1	26.2	13.3	(0.08)	2,880	2,791
E-334	177.5	12.0	Qpfnl	10.0	3.26	0.3	25.5	105.5	0.66	24.7	105.5	0.63	9.2	8.9	6.0	0.03	11.2	13.0	7.9	(0.12)	1,521	1,028
E-334	178.0	11.5	Qpfnl	20.1	7.20	0.4	25.4	103.7	0.70	26.7	103.7	0.66	16.7	16.6	11.0	(0.10)	18.3	20.5	11.0	(0.10)	2,220	2,220
E-334	178.5	11.0	Qpfnl	40.2	15.50	0.4	24.9	104.0	0.70	26.6	104.0	0.65	30.2	29.7	14.8	0.00	30.3	30.3	14.8	0.00	2,885	2,885
E-337	288.0	78.5	Qpfnl	10.0	4.00	0.4	27.7	100.8	0.74	27.8	100.8	0.70	11.5	11.8	16.0	(0.27)	20.0	28.7	16.0	(0.3)	1,503	1,414
E-337	289.0	77.5	Qpfnl	20.6	20.10	1.0	24.6	96.2	0.76	25.7	96.2	0.78	33.0	22.3	15.0	0.27	35.1	26.9	15.0	0.3	2,312	1,622
E-337	289.5	77.0	Qpfnl	40.3	16.50	0.4	28.9	103.1	0.80	27.0	103.1	0.67	33.0	30.0	16.5	0.09	33.0	30.1	16.5	0.1	3,927	3,927
E-337	326.0	40.5	Qpfnf	10.1	3.50	0.4	23.5	99.5	0.70	26.5	99.5	0.73	15.7	19.0	18.7	(0.20)	22.3	29.7	18.7	(0.2)	1,194	559
E-337	326.5	40.0	Qpfnf	20.1	8.00	0.4	24.1	100.1	0.71	26.0	100.1	0.72	23.6	24.6	26.2	(0.21)	34.2	45.3	26.2	(0.2)	3,001	2,264

Notes:

- a) Vertical datum = Metro. All locations surveyed to +/- 0.1 foot accuracy with the exception of some off alignment borings (noted as scaled on the log) which were estimated.
- b) Failure defined by maximum principal stress ratio.
- c) Failure defined by maximum principal stress difference.
- d) Initial secant modulus E_i taken at 0.1% strain.
- e) Young's secant modulus E_{50} taken at 50% of q at failure @ R_{max} .
- f) For all Geologic Unit descriptions, see Figure 3-1.

Table 7-15 Summary of K_0 -Consolidated Undrained Triaxial Tests
CENTRAL CONTRACT
Brightwater Conveyance System

Boring No.	Sample Top Depth (ft)	Elevation (ft) ^a	Geologic Unit	σ_v (ksf)	σ_h (ksf)	K_0	Initial Conditions			After Consolidation			Failure @ R_{max} ^b				Failure @ q_{max} ^c				E_i ^d (ksf)	E_{50} ^e (ksf)
							W (%)	γ_{dry} (pcf)	e	W (%)	γ_{dry} (pcf)	e	p (ksf)	p' (ksf)	q_{max} (ksf)	A_f	p (ksf)	p' (ksf)	q_{max} (ksf)	A_f		
BRIGHTWATER TUNNEL 2																						
E-324	297.0	47.6	Qpogf	19.7	7.90	0.4	19.9	107.2	0.61	21.1	108.6	0.58	41.7	40.1	25.1	(0.14)	42.8	41.9	26.1	(0.15)	2,797	709

Notes:

- a) Vertical datum = Metro. All locations surveyed to +/- 0.1 foot accuracy with the exception of some off alignment borings (noted as scaled on the log) which were estimated.
- b) Failure defined by maximum principal stress ratio.
- c) Failure defined by maximum principal stress difference.
- d) Initial secant modulus E_i taken at 0.1% strain.
- e) Young's secant modulus E_{50} taken at 50% of q at failure @ R_{max} .
- f) For all Geologic Unit descriptions, see Figure 3-1.

Table 7-15 Summary of K_0 -Consolidated Undrained Triaxial Tests
WEST CONTRACT
Brightwater Conveyance System

Boring No.	Sample Top Depth (ft)	Elevation (ft) ^a	Geologic Unit	σ_v (ksf)	σ_h (ksf)	K_0	Initial Conditions			After Consolidation			Failure @ R_{max} ^b				Failure @ q_{max} ^c				E_i ^d (ksf)	E_{50} ^e (ksf)
							W (%)	γ_{dry} (pcf)	e	W (%)	γ_{dry} (pcf)	e	p (ksf)	p' (ksf)	q_{max} (ksf)	A_f	p (ksf)	p' (ksf)	q_{max} (ksf)	A_f		
BRIGHTWATER TUNNEL 4																						
E-408	413.3	163.4	Qpfnl	55.2	23.6	0.4	20.0	106.5	0.61	21.7	107.9	0.59	57.7	44.5	25.5	0.09	59.7	50.2	27.5	0.02	5,102	5,102
E-408	414.0	162.7	Qpfnl	35.3	17.4	0.5	25.9	100.0	0.70	24.2	103.9	0.65	43.0	28.6	16.8	0.17	43.8	30.5	17.7	0.13	5,011	5,011
E-409	383.0	113.4	Qpogl	20.7	5.7	0.3	16.0	118.4	0.47	17.9	119.7	0.43	28.3	20.2	13.1	(0.05)	35.3	33.3	20.1	(0.19)	3,434	3,434
E-409	383.5	112.9	Qpogl	55.1	22.9	0.4	19.6	112.2	0.53	18.5	117.6	0.46	57.6	47.3	27.6	0.06	60.6	55.8	30.6	(0.04)	5,814	5,814
E-412	248.5	152.2	Qpfnf	10.1	10.0	1.0	20.8	103.6	0.69	22.8	100.8	0.70	39.5	33.2	20.8	(0.06)	41.8	36.9	23.1	(0.08)	1,341	578
E-412	249.0	151.7	Qpfnf	20.1	7.4	0.4	21.0	106.2	0.64	23.0	106.3	0.62	49.1	50.5	33.0	(0.15)	49.1	50.5	33.0	(0.15)	2,271	1,097
E-412	249.5	151.2	Qpfnf	39.9	16.6	0.4	21.5	105.3	0.61	20.1	108.4	0.58	54.3	47.8	29.1	(0.04)	60.6	58.8	35.4	(0.10)	5,573	5,159
E-412	258.0	142.7	Qpogm	20.2	4.9	0.2	35.4	85.6	1.01	36.1	89.1	0.93	25.8	12.9	8.6	0.04	25.8	12.9	8.6	0.04	1,720	1,720
E-412	258.5	142.2	Qpogm	5.0	2.0	0.4	25.1	97.4	0.74	26.6	100.7	0.71	16.1	3.5	1.8	0.07	16.2	3.8	1.9	0.01	175	175

Notes:

- a) Vertical datum = Metro. All locations surveyed to +/- 0.1 foot accuracy with the exception of some off alignment borings (noted as scaled on the log) which were estimated.
- b) Failure defined by maximum principal stress ratio.
- c) Failure defined by maximum principal stress difference.
- d) Initial secant modulus E_i taken at 0.1% strain.
- e) Young's secant modulus E_{50} taken at 50% of q at failure @ R_{max} .
- f) For all Geologic Unit descriptions, see Figure 3-1.